PART 0 DESIGN STANDARDS

0.01 GENERAL DESIGN GUIDELINES

A. All structural and non-structural grout shall contain no metallic elements.

B. All grouts shall be non-shrink.

C. Coordinate grout strength with project requirements.

D. Coordinate the manufacturer's recommended practices with the method of application, especially dry pack method.

PART 1 GENERAL

1.01 TESTING

A. Contractor shall perform quality control testing for structural grout to assure minimum load carrying capacities are met. Such testing shall be at the Contractor's expense. Upon request, test results shall be distributed to Architect and Owner.

B. Owner may request testing by Owner's Testing Agent if Owner so desires. Contractor shall fully cooperate in providing access and samples for Testing Agent.

PART 2 PRODUCTS No standards

PART 3 EXECUTION No standards

END OF SECTION 03600