PART 0 DESIGN STANDARDS

0.01 GENERAL DESIGN GUIDELINES

A. Coordinate with standards in Section 03300.

B. Specify types of concrete finishes for all exterior and interior exposed concrete.

C. Specify concrete finishes for all interior concrete whether covered with finish flooring or left exposed.

D. Specify curing and sealing compound for all exterior slabs. Compound shall be resistant to de-icing chemicals.

E. Specify a finished clear sealer for all interior slabs that are to remain exposed in the finished work (Exception: Mechanical chases).

F. Coordinate curing methods with floor finish manufacturer's concrete curing requirements.

G. Coordinate curing methods with waterproofing and dampproofing materials.

H. Scarification shall be accomplished by sandblasting or shotblasting of slab prior to installation of flooring.

I. Specify site samples for all special concrete finishes.

J. Exposed aggregate and other heavy/rough exposed finishes are prohibited.

K. Use of pigmented sealers and concrete stains is prohibited without approval of the DPS Project Manager.

L. Use of non-dissipating curing and sealing compound is prohibited.

M. Acid washing is prohibited unless fully extracted.

PART 1 GENERAL No standards

PART 2 PRODUCTS No standards

PART 3 EXECUTION No standards

END OF SECTION 03345